Load Additions in the Load Forecast (MW) (Cumulative)			
Load Type	**End of Year 2 (2027)**	**End of Year 5 (2030)**	**End of Year 10 (2035)**
Data Centers	**6,700**	**23,000**	**25,000**
Cryptocurrency Mining Facilities	**4,500**	**7,500**	**8,500**
Hydrogen Electrolysis	**3,000**	**7,902**	**9,100**
Industrial Manufacturing Load	**2,800**	**7,100**	**7,600**

For 2025, the ERCOT transmission service providers (TSP) had once again reported a significantly larger-than-normal amount of contracted large loads that they asked to be included in the *2025 Long-Term Load Forecast* and *Regional Transmission Planning Study*. Due to the large amount of large-load requests for 2025, ERCOT has applied adjustment factors to these requests. ERCOT has adjusted the large-load projections provided by the TSPs based on the patterns observed by recent projects. The first adjustment was based on the average project delay of 180 days from the original project requested energization date for projects with in-service dates in 2022 through 2024. The next adjustment was applied to Data Centers. ERCOT studied requested MWs versus the peak consumption by data center site for data centers with in-service dates in 2022 through 2024. The average peak consumption per site was 49.8% of the requested MW. This factor was applied to all non-crypto data center load additions. The final adjustment used the percentage of previously filed officer letter projects with in-service dates in 2024 that have energized (55.4%). This percentage is based on percentage of loads energized.

The PUCT is developing criteria for including large loads in ERCOT's load forecasts along the lines of criteria applicable to generation projects (for example, the large-load customer has executed and securitized an interconnection agreement or meets other criteria demonstrating a firm commitment to interconnecting the load).

Demand-Side Management

Signed into law in June 2025, Texas Senate Bill 6 directs the PUCT to establish uniform large-load interconnection standards that, among other things, provide ERCOT with new large-load curtailment management tools and ERCOT's authority to direct (or require transmission service providers to direct) large loads to curtail their load prior to and during declared energy emergency situations. The following table shows the total large loads and their curtailment amounts included in the "Controllable and Dispatchable Demand Response" line items.

Summer	Total LL (MW)	LL Curtailment (MW)		Winter	Total LL (MW)	LL Curtailment (MW)
2025 (S)	3864.4	1,313.9		2025-26 (W)	9112.9	8,227.7
2026 (S)	12355.4	8,853.5		2026-27 (W)	17289.8	15,909.3
2027 (S)	21665.7	17,171.5		2027-28 (W)	31590.8	29,408.9
2028 (S)	38583.3	32,716.5		2028-29 (W)	45249.3	42,298.1
2029 (S)	45681.1	38,932.6		2029-30 (W)	55533.1	51,981.4
2030 (S)	55964.9	48,175.5		2030-31 (W)	60917.9	57,010.6
2031 (S)	61349.7	52,764.3		2031-32 (W)	64863.6	60,672.7
2032 (S)	65295.4	55,985.9		2032-33 (W)	66370.5	62,017.8
2033 (S)	66802.3	56,890.6		2033-34 (W)	67764.7	63,256.0
2034 (S)	68196.5	57,688.4		2034-35 (W)	69032.1	64,373.6
2035 (S)	69463.9	58,365.6		2035-36 (W)	69805.1	65,043.3

Distributed Energy Resources

DERs that register with ERCOT to participate in wholesale energy and/or ancillary services markets are modeled and dispatched in ERCOT transmission planning studies similarly to transmission-connected resources participating in those markets. For DERs not participating in those markets, ERCOT relies on member Transmission and Distribution Service Providers (TDSPs) to provide information about individual DERs on their systems for shorter-term reliability and economic impact studies, typically a one-to-six-year time frame.

ERCOT has proposed rule changes mandated by the Texas Legislature to establish a process to collect comprehensive data from Distribution Service Providers for so called "Unregistered Distributed Generators" (primarily rooftop solar systems). The data will be collected on a substation level and will include information to be used for network modeling and analysis, including aggregate reactive power capability and status of PUCT voltage/frequency ride-through requirements.

Generation

In 2024, ERCOT received notices of suspension of operations for three gas-steam units in the San Antonio area. Reliability impact studies indicated that all three were needed to manage the South Texas Interconnection Reliability Operating Limit (IROL) established in 2024. As a result, ERCOT signed